



# Concrete floor Repairs

Installation commences with damaged floor being broken out with manual breaker

Over the recess specifically designed reinforced Mesh t section pieces designed and welded for each project fully supported on its inner connecting rods. Once finished floor level is poured over biscuit style precast top slab leaving a flush and level finished floor.

All waste to be disposed of in a safe and controlled manner at an appropriate site



All TaylorMade operatives and there subcontractors will observe the company safety policy on the wearing and inspection of safety equipment. Operatives will wear approved PPE at all times. any lifting equipment test certificates necessary will be shown on request to the principal contractor. Under no circumstances will other personnel or equipment be allowed to encroach on our specific work area until the work in process is complete or by the express permission of the team leader who will ensure that any lifting or moving operation is satisfactory completed before access is granted . all welfare facilities will be afforded by the principal contractor by the way of an attendance and shall be in accordance with the " construction regulations" and any other relevant legislation.